



**CITY OF FORT DODGE
ENGINEERING DIVISION**

Municipal Building, 819 1st Avenue South, Fort Dodge, Iowa 50501

March 11, 2025

Sent Via: E-mail

**ADDENDUM # 1
TO PLANS AND SPECIFICATIONS FOR:**

2025 PCC Patch Project

To all plan holders:

The plans and specifications for the above referenced project shall be changed as follows:

Sheet B.1

- The description for Item #1, 8" PCC Removal, incorrectly references 10" PCC removal. Said item description is revised to read, "Item shall include, but is not limited to, 8" PCC removal, sawing, removing and disposing of existing pavement and reinforcing, and restore subgrade as specified in SUDAS 7040 3.03. Sawcut is considered incidental. Joint sealing on the patch perimeter and within the patch shall be considered incidental."
- The description for Item #2, 10" PCC Full Depth Patch, incorrectly references 12" PCC placement. Said item description is revised to read, "Item shall include, but is not limited to, the placement of 10" PCC, or 2 inches thicker than the removed PCC material. Tie bars and dowel bars shall be considered incidental to the patch. Moisten the subgrade. Conform to Section 7010 on bars, forms, patch, finish, and jointing, all of which are considered incidental to the patch.

Sheet C.1-D.3

- CD Joints are required for transverse joints in patches greater than 15' long. See SUDAS Figure 7040.102 replacing C joints with CD.

THIS ADDENDUM #1 SHALL BE ACKNOWLEDGED WITH THE BIDDER'S PROPOSAL.

A handwritten signature in blue ink that reads "Austin Morrow".

Austin Morrow, PE
City Engineer